

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

*6-30/99*

**SAGINAW COUNTY REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED/FILED

For corners in

SAGINAW  
(County)

KOCHVILLE TOWNSHIP

Located in: Corner Code #

- 1. Public Land Survey T13 N R 4 E D-9  
T      R
- 2. Property Controlling in Section S      T      R       
S      T      R
- 3. Miscellaneous Property in Sec. S      T      R       
S      T      R

1999 SEP 29 A 8 08

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

LIBER **2144** PAGE **786**

*Liber 8 Page 51*

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Brian D Ferguson, in a field survey on JUNE 28, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

WOOD POST SET BY J. WAMPLER IN 1822, NO EVIDENCE OF ORIGINAL CORNER REMAINS.  
LCRC BY JOHN MARTIN IN 1974, L 3, PG 32  
LCRC BY LLOYD MCGINNIS IN 1977, L 4, PG 24  
SURVEYS RECORDED IN L1563, PG 1458, L 1705, PG 917 & L 1801, PG 305

*SURVEY & RE...*  
**MAR 09 2000**  
**SECTION**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE IN MONUMENT BOX W/O COVER  
LCRC L 4, PG 24, SW 133.3' TO NE COR. HSE/GAR, MEA. 133.34'  
LCRC L 3, PG 32, SW 60.83' TO FCE 4" PINE, MEA. 59.60' FCE 36" MAPLE  
LOCATION VERIFIED BY RECORDED DISTANCES TO ADJOINING SECTION CORNERS

ACCEPTED BY PEER GROUP AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" RE-BAR & 3" BRASS CAP IN MONUMENT BOX  
S50W 59.60' NAIL IN N FCE 36" MAPLE  
N10E 44.50' NAIL IN W FCE 6" ELM  
N45W 33.18' 1/2" REBAR FLUSH W/ GROUND  
N20E 34.55' 1/2" REBAR ON S. DITCH LINE

Signed by *B D Ferguson*  
Surveyor's Michigan License No. 26454

Date SEPTEMBER 23 1999

