

Saginaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 7 Page 9.

For corners in

<u>Saginaw</u> (County)	Located in:	Corner Code #
Kochville Township		
1. Public Land Survey	T <u>13</u> N R <u>4</u> E	<u>E-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

HILDRED M. DODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY HIGH.

SEP 27 11 45 AM 1996

RECORDED & FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael J. MacDonald, in a field survey on August 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-7 Post set by J. Wampler D.S. in 1822.

1993 notes by Spicer - fnd 1/2" rod in monument box.
Recorded Surveys: L. 1772, P. 2214; L. 1734, P. 675; L. 1584, P. 2036; L. 1445, P. 121. (Saginaw County)
L.C.R.C. - L. 2, P. 177 - by J. Martin 3/4" iron pipe. (Bay County)
Recorded Surveys: L. 834, P. 459; L. 661, P. 64. (Bay County)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 Fnd 1/2" x 36" rebar in monument box at E edge of box.

Recorded Witnesses: NW 53.56' (53.74' - R) to face of T.P.
 1993 notes by Spicer indicate rebar in monument box at E-7 was used to reestablish position of D-7.
 Monument accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 Moved monument box and replaced 1/2" rebar with Bay County Remonumentation cap on 5/8" x 24" rebar in monument box.

N 40° E 56.30' to nail and tag in NW face of pole.
 N 45° W 54.00' to nail and tag in SW face of pole.
 S 40° W 59.95' to nail and tag in NW face of pole.
 S 45° E 42.22' to chiseled "x" on W rim of MH.



Signed by Michael J. MacDonald
 Surveyor's Michigan License No. 22438

Date 25 Sept 96

MAY 1 6 1997