

SAGINAW COUNTY REMONUMENTATION

RECORDED/FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 29 A 8 08

For corners in

KOCHVILLE TOWNSHIP

Located in: Corner Code #

SAGINAW
(County)

1. Public Land Survey T 13 N R 4 E E-8
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

LIBER 2144 PAGE 784

Liber 8 Page 49

Register of Deeds Stamp & File Number

I, Brian D Ferguson, in a field survey on JUNE 28, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-8 WOOD POST SET BY J. WAMPLER IN 1822, NO EVIDENCE OF ORIGINAL CORNER REMAINS
LCRC BY DUANE LEDY IN 1988, L 6, PG 40
SURVEYS RECORDED IN L 1584, PG 2036, L 1721, PG 224, L 1734, PG 675 & L 1755, PG 958

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8 FOUND 3/4" PIPE PER LCRC AND RECORDED SURVEYS
LOCATION VERIFIED BY COMMON WITNESSES AND DISTANCES TO ADJOINING SECTION CORNERS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8 SET 5/8" REBAR W/ 3" BRASS CAP IN MONUMENT BOX
EAST 51.40' NAIL IN W FCE PWR POLE
N60E 126.90' SW COR GARAGE @ HSE #7480
WEST 32.67' 1/2" REBAR FLUSH W/GROUND
S20W 69.32' 1/2" REBAR EAST DITCH LINE

Signed by Brian D Ferguson
Surveyor's Michigan License No. 26454

Date SEPTEMBER 23 1999

