

7-21/808

SAGINAW COUNTY REMONUMENTATION

RECORDED/FILED

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

	<b>KOCHVILLE TOWNSHIP</b>	
<u>SAGINAW</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13</u> N R <u>4</u> E	<u>E-10</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1999 SEP 29 A 8:08

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

LIBER 2144 PAGE 788

*Liber 8 Page 53*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Brian D Ferguson, in a field survey on JUNE 28, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

WOOD POST SET BY J. WAMPLER IN 1822, NO EVIDENCE OF ORIGINAL CORNER REMAINS  
LCRC BY JOHN MARTIN IN 1974, L 3, PG 32  
SURVEY RECORDED IN L 1541, PG 670  
UN-RECORDED SURVEYS BY RC ASSOCIATES

SURVEY &  
RECORDATION  
MAR 09 2000

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE IN MONUMENT BOX AT LOCATION PER SURVEYS  
ALL WITNESSES FROM LCRC GONE  
VERIFIED LOCATION BY DISTANCES TO ADJOINING SECTION CORNERS FROM SURVEYS

SECTION

ACCEPTED BY PEER GROUP AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" REBAR W/ 3" BRASS CAP IN MONUMENT BOX  
S25W 97.64' NE COR HSE #6485  
WEST 24.81' TOP CTR CMP  
S40W 94.32' FCE 30" BOX ELDER TREE  
WEST 3.42' WEST ENDGE OF PAVEMENT

Signed by Brian D Ferguson  
Surveyor's Michigan License No. 26454

Date SEPTEMBER 27 1999

