

Saginaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 7 Page 79

For corners in

Saginaw (County)	Located In:	Corner Code #
Kochville Township		
1. Public Land Survey	T <u>13NR</u> 4E	<u>F-7</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

MILDRED M. DODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.
 SEP 27 11 44 AM 1986
 RECORDED & FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael J. MacDonald, in a field survey on August 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7						●							
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-7 Set by J. Wampler D.S. in 1822.
Recorded Surveys: L. 1772, P. 2214. (Saginaw County)
L. 860, P. 42. (Bay County)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7 Fnd 5/8" rebar 39" long near surface and a 3/4" pipe 24" below surface 0.20' S and 0.35' W of rebar.
1978 survey by Edmands calls for a 3/4" pipe 18" below surface.
1994 Spicer notes indicate pipe not found and corner reset with 5/8" rebar recorded witnesses as follows: N 3.0' to S edge of pavement N 53.26' (53.2' - R to face) to nail and tag in wood fence post 3/4" pipe accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7 Set Saginaw County Remonumentation cap on 5/8" x 18" rebar in monument box over 3/4" pipe left in place.
S 80° E 173.75' to nail and tag in N face of pole.
S 75° W 132.61' to nail and tag in N face of pole.
N 53.26' to nail and tag in W face of wood post.
S 80° W 124.40' to E end of 48" CMP.



Signed by Michael J. MacDonald Date 25 Sept 96
Surveyor's Michigan License No. 22438

MAY 16 1997