

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

9-1 *[Signature]*

SAGINAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED/FILED

1999 SEP 29 A 8 05

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

LIBER 2144 PAGE 761

Liber 8 Page 26

Register of Deeds Stamp & File Number

For corners in

KOCHVILLE TOWNSHIP

<u>SAGINAW</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13 N</u> R <u>4 E</u>	<u>G-8</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Brian D Ferguson, in a field survey on JUNE 28, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21	●	22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

WOOD POST SET BY J. WAMPLER IN 1822, NO EVIDENCE OF ORIGINAL CORNER REMAINS
LCRC BY ARTHUR LEACH IN 1974, L 3, PG 60
LCRC BY LLOYD MCGINNIS IN 1977

SURVEY &
RE...

MAR 29 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE IN MONUMENT BOX
NO WITNESSES FROM LCRC'S REMAIN. VERIFIED LOCATION FROM SECTION BREAK IN 1974 BY ARTHUR LEACH.
DISTANCES NORTH AND SOUTH TO ADJOINING SECTION CORNERS VERIFY LOCATION AS SAME.

ACCEPTED BY PEER GROUP AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" REBAR W/ 3" BRASS CAP IN MONUMENT BOX
N35W 87.05' NAIL IN E FCE PWR POLE
N35E 52.75' SET REBAR 1' W OF DITCH
S45W 44.05' SET REBAR 1' E OF DITCH
S40E 40.04' SET REBAR 1' W OF DITCH

Signed by *Brian D Ferguson*
Surveyor's Michigan License No. 26454

Date SEPTEMBER 23, 1999

