

9-1 BDF

SAGINAW COUNTY REMONUMENTATION

RECORDED/FILED

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 29 A 8 05

For corners in

KOCHVILLE TOWNSHIP

<u>SAGINAW</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13 N</u> R <u>4 E</u>	<u>G-9</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MILDRED M. DOBAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

LIBER 2144 PAGE 762

Liber 8 Page 27

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian D Ferguson, in a field survey on JUNE 29, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

WOOD POST SET BY J. WAMPLER IN 1822, NO EVIDENCE OF ORIGINAL CORNER REMAINS
LCRC BY EUGENE GOSS IN 1971, L 2, PG 78
LCRC BY RON PREVOST IN 1979, L 5, PG 22
SURVEYS RECORDED IN L 1366, PG 58, L 1366, PG 61 & L1892, PG 53

SURVEY &
RF
MAR 9 2000
SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2 IRON BAR AT LOCATION PER RECORDED SURVEYS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ACCEPTED BY PEER GROUP AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

SET 5/8" REBAR W/ 3" BRASS CAP IN MONUMENT BOX
S35E 38.20' TOP CTR AMERTECH RISER
N55E 51.52' TOP CTR HYDRANT
S55W 63.48' MAG NAIL S SIDE PWR POLE
N60W 61.30' TOP CTR M BELL RISER

Signed by BDF Ferguson
Surveyor's Michigan License No. 26454

Date _____

