

9-1 [Signature]

SAGINAW COUNTY REMONUMENTATION

RECORDED/FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 29 A 8 06

For corners in

KOCHVILLE TOWNSHIP

SAGINAW Located in: Corner Code #
(County)

- 1. Public Land Survey T13 N R 4 E G-11
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

LIBER 2144 PAGE 764

Lib 8 Page 29

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Brian D Ferguson, in a field survey on JUNE 30, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2			
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

WOOD POST SET BY J. WAMPLER IN 1822, NO EVIDENCE OF ORIGINAL CORNER REMAINS
LCRC BY GERALD MCKELVEY IN 1972, L 1, PG 199
SURVEY RECORDED IN 1541, PG 670

RECORDED & FILED

MAR 9 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE IN MONUMENT BOX. LOCATION VERIFIED BY WITNESSES FROM LCRC, VARIOUS UN-RECORDED SURVEYS AND DISTANCES TO ADJOINING SECTION CORNERS FROM SAID SURVEYS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ACCEPTED BY PEER GROUP AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

SET 5/8" REBAR W/ 3" BRASS CAP IN MONUMENT BOX
S50E 61.84' TOP CTR HYDRANT
S45W 37.12' NAIL & TAG SE FCE PWR POLE
N45E 37.46' NAIL & TAG IN SW FCE PWR POLE
N50W 41.56' REBAR SE SIDE DITCH

Signed by [Signature]
Surveyor's Michigan License No. 26454

Date SEPTEMBER 23, 1999

