

Saginaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 7 Page 77

For corners in

Saginaw (County)	Located In:	Corner Code #
Kochville Township		
1. Public Land Survey	T <u>13NR</u> <u>4E</u>	<u>H-7</u>
	T <u> </u> <u> </u>	<u> </u>
	T <u> </u> <u> </u>	<u> </u>
	T <u> </u> <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

MILDRED M. DODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

SEP 27 11 44 AM '96

RECORDED & FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael J. MacDonald, in a field survey on August 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-7 Post set by J. Wampler D.S. in 1822.
Section break by Saginaw County Surveyor H. Gary in 1880.

L.C.R.C. - L. 1, P. 221 - E. Goss find 3/8" iron. (Bay County)
Recorded Surveys - L. 655, P. 388; L. 1150, P. 780; L. 729, P. 594. (Bay County)

L.C.R.C. - L. 4, P. 25 - L. McGinnis found 3/8" Iron. L. 3, P. 79 - J. Martin found 1/4" Iron. (Saginaw County)
Recorded Surveys - L. 1783, P. 1070; L. 1215, P. 288. (Saginaw County)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 Found 1 1/2" iron pipe at surface per Recorded Survey L. 1783, P. 1070 (Found 1" pipe).

Recorded Witnesses as follows:
NE 54.15' to face of 30" Maple (54.3' - R to 30" Oak).
NE 100.10' (100.15' - R) to SW cor of block foundation of Hse.
SE 107.20' (107.22' - R) to NW cor of block foundation of Hse.
NE 44.12' (44.15' - R) to centerline stem of hydrant.
SE 65.14' (65.1' - R) to face of utility pole.
Monument accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 Replaced 1 1/2" pipe with Saginaw Remonumentation cap on 5/8" x 18" rod in monument box.

S 35° W 51.05' to nail and tag in E face of pole.
S 40° E 106.98' to NW cor of vinyl siding of Hse. #7970.
N 45° E 44.13' to top center of hydrant.
N 25° W 66.24' to nail and tag in E face of pole.



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 25 Sept 96

MAY 16 1997

COMMISSION