

7-21 BDF

SAGINAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED/FILED

1999 SEP 29 A 8 06

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

LIBER 2144 PAGE 767

Lib 8 Page 32

Register of Deeds Stamp & File Number

For corners in

KOCHVILLE TOWNSHIP

<u>SAGINAW</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13</u> N R <u>4</u> E	<u>H-11</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian D Ferguson, in a field survey on JUNE 30, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6				4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

WOOD POST SET BY J. WAMPLER IN 1822, NO EVIDENCE OF ORIGINAL CORNER REMAINS
LCRC BY GERALD MCKELVEY IN 1972, L 1, PG 192
LCRC BY JOHN RAUSER IN 1999, UNKNOWN L & PG
SURVEYS RECORDED IN L 1715, PG 865 & L 1739, PG 1872

SURVEY &
RECORDED

MAR 19 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE IN MONUMENT BOX PER WITNESSES OF LCRC'S. LOCATION ALSO VERIFIED FROM DISTANCES ON RECORDED AND UN-RECORDED SURVEYS TO ADJOINING SECTION CORNERS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" REBAR W/ 3" BRASS CAP IN MONUMENT BOX
SOUTH 44.29' NAIL & TAG W FCE PWR POLE
S50E 90.30' TOP CTR HYDRANT
NORTH 46.65' NAIL IN 20" BOX ELDER
N45E 53.50' MDOT NAIL & TAG NW SIDE 20" CHESTNUT

Signed by Brian D Ferguson
Surveyor's Michigan License No. 26454

Date SEPTEMBER 23 1999

