

Saginaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Lib 7 Page 91*

For corners in

<u>Saginaw</u> (County)	Located In:	Corner Code #
Kochville Township	T <u>13N</u> R <u>4E</u>	<u>1-7</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED & FILED  
SEP 27 11 45 AM 1986  
MILDRED H. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael J. MacDonald, in a field survey on August 20, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-7 Set by J. Mullet in 1839.  
Stake found by Saginaw County Surveyor, H. Gary in 1879.  
Undated Witness Card by Francis Engineering found two of Gary's Witness trees.

L.C.R.C. - L. 3, P. 79 - J. Martin found 1/4" rod.  
Recorded Surveys - L. 1783, P. 1070.  
L.C.R.C. - L. 1, P. 221 - E. Goss frnd 3/4" pipe 16" deep -  
set 3/8" iron over pipe. (Bay County)  
Recorded Surveys - L. 834, P. 484. (Bay County)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7 Found 1/2" pipe in monument box per Recorded Survey - L. 1783, P. 1070.

Recorded Witnesses as follows:  
N 45° W (N 55° W - MDOT) 81.7' (81' - MDOT) to 18" Apple stump.  
SW 79.70' (79.58' - R) to PK nail in N side of leaning utility pole.  
S SW 28.13' to chiseled "x" in T/curb.  
N NW 32.42' (32.45' - R) to chiseled "x" in T/curb.  
Monument accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7 Replaced 1/2" pipe in monument box with Bay County Remonumentation cap on 5/8" x 24" rerod.  
  
S 68° W 75.50' to nail and tag in N face of pole.  
N 07° E 164.05' to nail and tag in E face of 8" Ash.  
N 18° W 32.40' to chiseled "x" in top of curb.  
S 60° E 68.54' to nail and plastic cap in NW face of pole.  
N 56° E 83.42' to chiseled "x" on E'ly rim of sanitary MH.



Signed by Michael J. MacDonald  
Surveyor's Michigan License No. 22438

Date 25 Sept 96

REMONUMENTATION

MAY 18 1997