

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

9-22-99

SAGINAW COUNTY REMONUMENTATION

RECORDED/FILED

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 29 A 8 07

For corners in

KOCHVILLE TOWNSHIP

<u>SAGINAW</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13</u> N R <u>4</u> E	<u>1-12</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

LIBER 2144 PAGE 772

Liber 8 Page 37

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Brian D Ferguson, in a field survey on JUNE 26, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		8		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

WOOD POST SET BY J. WAMPLER IN 1822, NO EVIDENCE OF ORIGINAL CORNER REMAINS
 LCRC BY STEPHEN SOLTIS IN 1973, L 2, PG 135
 LCRC BY RON PREVOST IN 1979, L 4, PG 224
 LCRC BY JOHN RAUSER IN 1999, UNKNOWN L & PG
 SURVEYS RECORDED IN LIBER 1761, PG 772; L 1375, PG 181; L1715, PG 865

SURVEY &
 MAR 9 2000
 SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BOAT SPIKE IN MONUMENT BOX PER WITNESSES OF LCRC'S AND SURVEYS. VERIFIED LOCATION BY DISTANCES TO ADJOINING SECTION CORNERS FROM SURVEYS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ACCEPTED BY PEER GROUP AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

SET 5/8" REBAR W/ 3" BRASS CAP IN MONUMENT BOX
 S30E 90.30' CTR HYDRANT
 N55E 55.25' MDOT NAIL & TAG S SIDE PWR POLE
 N75W 46.15' NAIL & FLAG NE FCE PWR POLE
 S45W 56.95' NAIL & FLAG SE FCE PWR POLE

Signed by Brian D Ferguson
 Surveyor's Michigan License No. 26454

Date _____

