

2-21 *[Signature]*

SAGINAW COUNTY REMONUMENTATION

RECORDED/FILED

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 1999 SEP 29 A 8:07

For corners in

KOCHVILLE TOWNSHIP

Located in: Corner Code #

SAGINAW
(County)

- 1. Public Land Survey T13 N R 4 E J-11
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

LIBER 2144 PAGE 774

Index 8 Page 39

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Brian D Ferguson, in a field survey on JUNE 26, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

WOOD POST SET BY J. WAMPLER IN 1822, NO EVIDENCE OF ORIGINAL CORNER REMAINS
LCRC BY JOHN MARTIN IN 1974, L 3, PG 79
LCRC BY JOHN RAUSER IN 1999, UNKNOWN L & PG
RECORDED SURVEY IN L 1783, PG 2072

RECORDED &
INDEXED
MAR 9 2000
SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" ROD IN MONUMENT BOX PER WITNESSES FROM LCRC'S AND SURVEY. VERIFIED LOCATION OF CORNER PER DISTANCE FROM RECORDED SURVEY TO ADJOINING SECTION CORNERS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ACCEPTED BY PEER GROUP AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

SET 5/8" REBAR W/ 3" BRASS CAP IN MONUMENT BOX
SOUTH 43.00' IRON W/CAP
S45W 82.80' PK NAIL SE FCE PWR POLE
S45E 50.76' SPIKE IN CHINESE ELM
NORTH 30.40' TOP CTR HYDRANT

Signed by *Brian D Ferguson*
Surveyor's Michigan License No. 26454

Date SEPTEMBER 24 1999

