

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION

RECORDED/FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 29 A 8:07

For corners in

KOCHVILLE TOWNSHIP

Located in: Corner Code #

SAGINAW
(County)

- 1. Public Land Survey T13 N R 4 E K-8
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

LIBER 2144 PAGE 775

Liber 8 Page 46

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Brian D Ferguson, in a field survey on JUNE 26, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

WOOD POST SET BY J. WAMPLER IN 1822, NO EVIDENCE OF ORIGINAL CORNER REMAINS
LCRC BY JACK ERICKSON IN 1981, L 5, PG 125

SURVEY &
REGISTERED

MAR 9 2006

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" ROD IN MONUMENT BOX PER WITNESSES ON LCRC AND UN-RECORDED SURVEY. VERIFIED LOCATION FROM DISTANCES ON UN-RECORDED SURVEY TO ADJOINING SECTION CORNERS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ACCEPTED BY PEER GROUP AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER
- SET 5/8" REBAR W/ 3" BRASS CAP IN MONUMENT BOX
- S50E 76.18' NAIL & TAG NE FCE PWR POLE
- N45E 47.60' NAIL & TAG IN 20" TREE
- N75W 77.43' NAIL S FCE 4" ELM
- S45W 86.80' NAIL N FCE 4" ELM

Signed by Brian D Ferguson
Surveyor's Michigan License No. 26454

Date _____

