

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Saginaw
(County)
Kochville Township
1. Public Land Survey

Located In:	Corner Code #
T <u>13N</u> R <u>4E</u>	<u>M-7</u>
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

2. Property Controlling
in Section
3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

REGISTERED & FILED
SEP 27 11 44 AM 1996
MILDRED H. BODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

I, Michael J. MacDonald, in a field survey on September 31 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7 Post set by J. Mullett in 1839.
Undated Witness notes by CPCo - 1" square bolt.
Undated Bay County Road Commission Witness Notes - 1" iron rod.

Recorded Surveys: L. 1383, P. 509. (Bay County)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 Found boat spike 8" below surface - also found below boat spike 3/4" x 42" long bolt with 1 1/4" top on NW edge of large flat top rock 20" deep.

Recorded Witnesses:
NW 13.7' (13.7' - R)(13.77' - BCRC)(13.7 - CPCo) to SW cor bridge.
SW 29.02' (29.05' - CPCo) to NE cor bridge.
NE 18.36' (18.4' - R)(18.5' - BCRC) to SE cor bridge.
SE 48.52' (48.5' - R) to nail in W face of pole.
W 2744.67' (2744.75 - MDOT) to L-7, T13N, R4E.
Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 Replaced spike with Bay County Remonumentation cap on 5/8" x 24" rebar in monument box.
N 15° W 38.25' to NE cor of North guard rail post on W side of N'y bridge.
N 30° E 41.81' to NW cor of N guard rail post on E side of N'y bridge.
N 45° E 49.32' to nail in W face of pole.
S 45° E 48.53' to nail in W face of pole.
S 60° E 33.25' to NE cor of railroad rail gate post on S side of field drive.



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 25 Sept 96

MAY 16 1997