

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ 20 T. _____ 13 N. _____ 5 E. _____	_____ S., R. _____	C-7, D-7
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. _____, S., R. _____, E. _____, W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. _____, S., R. _____, E. _____, W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Saginaw Co

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>C-7 Set 4" x 36" Conc. mon. w/alum. cap Using data from 1955 survey by Spicer Engineering.</p>	<p>D-7 Set 4" x 10' P.V.C. pipe with 1" x 10' iron pipe inside w/alum. cap and filled with concrete. 10" above water surface Using data from 1955 survey by Spicer Engineering.</p>
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>C-7 NW Cor. Sec. 20 4" x 36" Conc. mon. w/alum. cap S85°W - 21.48' - 14" W. Ash, Spike & Tag N43°W - 37.00', 7" Popular, spike & tag N60°E - 62.53', 18" Twin W. Oak, spike & tag South - 19' - N. edge ditch @ water</p>	<p>D-7 N½ Cor. Sec. 20 4" x 10' conc. mon. w/alum. cap S20°E - 93.95' - Power Pole, spike & tag N85°E - 76.32' - Power Pole, spike & tag East - 40' - Dike South - 75' - Dike</p>
--	---

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE 3-29-84
CHIEF OF SURVEY AND
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

