

**SURVEY &
REMONUMENTATION**

APPROVED BY PEER GROUP
P.A. 345 OF 1990

MAR 12 1999

LIBER 2084 PAGE 237

BLD
SAGINAW COUNTY
9-16-98

**SAGINAW COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

SAGINAW COUNTY
(County)

Located in: BUEVA VISTA
Corner Code # _____

Lib 7 Page 215
MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.
1998 OCT -5 A 9:49
RECORDED/FILED
Register of Deeds Stamp & File Number

1. Public Land Survey	T <u>13N</u> R <u>5E</u>	<u>1-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, DALE L. WINIECKE, in a field survey on JUNE 2, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-7

- POST SET BY JOHN MULLETT D.S., APRIL 1840.
12" ASH, N51 1/2"W, 2 LINKS; 10" ASH N13"W, 1.63 LINKS.
- CERTIFICATE OF SURVEY, L.952, P.325, A. LEACH, PS#7235, (1983), FOUND 1/2" SOLID ROD.
- LCRC, L. 1632, P. 1092, A. LEACH, PS#7235, (1983), FOUND 1/2" SOLID ROD .
- CERTIFICATE OF SURVEY, L.1078, P.364, D. BURGIN, PS#29240 (1988), FOUND 1/2" IRON.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7

SEARCHED APPARENT LOCATION OF CORNER AND FOUND 5/8" IRON BAR 0.35' BELOW THE SURFACE OF THE ROAD. EXCAVATED TO CLAY AND FOUND NO OTHER OBJECTS.
ALL WITNESSES BY A. LEACH PS#7235 FROM THE CERTIFICATE OF SURVEY AND LCRC WERE GONE.
CHECKED WITNESSES FROM L. 1078, P. 364 ESE TO SPIKE IN U. POLE 67.5' (R) S75°E TO A NAIL IN THE NORTH FACE OF A U. POLE 67.44' (M); ENE TO CHISEL SQUARE IN E. END 7.5' CONCRETE CULVERT 58.05' (R), N 25°E TO THE SOUTHWEST CORNER OF A CHISELED SQUARE ON CONCRETE CULVERT 57.88' (M).
ACCEPTED 5/8" BAR AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7

SET 5/8" X 24" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX.
NORTH 7.5' TO CENTERLINE OF MUNGER ROAD.
EAST 1.0" TO CENTERLINE FRED ROAD.
S 75°E 67.44" TO NAIL IN NORTH FACE OF POWER POLE
N 25°E 57.88' TO THE SOUTHWEST CORNER OF CHISELED SQUARE ON 7' CONCRETE CULVERT
N 70°W 36.80" TO NAIL AND TAG IN SOUTH FACE OF LIGHT POLE

Signed by Dale Winiecke
Surveyor's Michigan License No. 41915

Date 3/24/98