

SAGINAW COUNTY REMONUMENTATION

RECORDED/FILED

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Saginaw

(County)

Located In: BUENA VISTA

Corner Code #

1. Public Land Survey

T 13N R 5E

K-7

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

1997 SEP 26 P 3: 29

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

LIBER 2027 PAGE 466

*Liber 7 Page 157*

Register of Deeds Stamp & File Numl

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Michael J. MacDonald, in a field survey on JULY 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K
2		6		5		4		3		2	
3											
4		7		8		9		10		11	
5											
6		18		17		16		15		14	
7											
8		19		20		21		22		23	
9											
10		30		29		28		27		26	
11											
12		31		32		33		34		35	
13											

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-7 SET POST, J. WAMPLER, 1821  
LYNN 14", N 70 1/2°W 7 L.  
BEECH 11" S 43 1/2° E 27 L.

L.C.R.C. L. 2, P. 148, GOSS, 1973, FND 3/4" PIPE  
RECORDED SURVEY, L. 832, P. 164, MACDONALD, 1977, FND. MON. BOX  
UNRECORDED BAY CO. SURVEY, BURGIN, 1993, FND. PINCHED PIPE IN MON. BOX

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

*B-8-97*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7 FOUND PINCHED PIPE IN MONUMENT BOX, LOCATION VERIFIED BY RECORDED WITNESSES. MONUMENT ACCEPTED AS THE BEST AVAILA EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7 REPLACED FOUND 3/4" PINCHED PIPE IN MONUMENT BOX WITH 5/8"x 18" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP  
N 50°E 29.01' SET PK IN TOP OF HEADWALL  
S 83°E 120.24' SET NAIL & TAG IN NORTH FACE UTILITY POLE  
S 35°E 83.01' SET NAIL & TAG IN NE FACE 24" ELM  
S 30°E 51.12' SET CAPPED 3/8" REROD  
S 58°W 36.22' SET CAPPED 3/8" REROD  
N 70°W 127.61' SET NAIL & TAG IN SOUTH FACE PP  
N 46°W 32.22' SET PK IN TOP CONC. HEADWALL  
N 42°W 45.53' FOUND SPIKE IN PP

SURVEY &  
REMONUMENTATION

MAR 18 1998



Signed by Michael J. MacDonald

SECTION \_\_\_\_\_

Date 9/25/97

Surveyor's Michigan License No. 22438