

**SAGINAW COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED/FILED

For corners in

Saginaw
(County)

Located In: BUENA VISTA
Corner Code #

1997 SEP 26 P 3: 29

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

LIBER 2027 PAGE 467

Liber 7 Page 158
Register of Deeds Stamp & File Number

1. Public Land Survey T13N R5E L-7
 T R
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Michael J. MacDonald, in a field survey on JULY 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-7 SET POST, J. WAMPLER D.S., 1821
NO RECORDED SURVEYS OR L.C.R.C.

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

8-8-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE. NO OTHER MONUMENTS FOUND IN THE AREA. MONUMENT ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 3/4" PIPE 0.8' WEST OF CENTERLINE OF ROAD TO THE NORTH, 5' NORTH OF THE CENTERLINE OF THE EAST-WEST ROAD. REPLACED 3/4" PIPE WITH 5/8" x 18" LONG REROD WITH SAGINAW COUNTY REMONUMENTATION CAP.

N 40°E 41.78' FOUND NAIL AND TAG IN WEST FACE U.P.
 N45°E 24.52' SET CAPPED 3/8" REROD
 S 35°E 40.25' SET CHISELED "X" WEST END CONC. PIPE
 S 30°E 27.62' SET CAPPED 3/8" REROD
 S 40°W 31.27' SET CAPPED 3/8" REROD
 S 45°W 42.75' FND. NAIL & TAG IN NW FACE U.P.
 N 35°W 22.95' SET CAPPED 3/8" REROD



Signed by Michael J. MacDonald

Date 9/25/97

Surveyor's Michigan License No. 22438 SURVEY & REMONUMENTATION

MAR 18 1998

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 197
 REVISED MAY 14, 197
 REVISED JAN., 198
 REVISED OCT., 199

SECTION