

SAGINAW COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED/FILED

1997 SEP 26 P 3:29

MILDRED M. DODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY, MI.

LIBER 2027 PAGE 468

Liber 7 Page 159
 Register of Deeds Stamp & File Num

For corners in

Saginaw
 (County)

Located In: BUENA VISTA

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>13N</u> R <u>5E</u> | <u>M-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael J. MacDonald, in a field survey on JULY 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	
1												
2	6			5			4			3		2
3												
4	7			8			9			10		11
5												
6	18			17			16			15		14
7												
8	19			20			21			22		23
9												
10	30			29			28			27		26
11												
12	31			32			33			34		35
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-7 SET POST, J. WAMPLER 1821
- B. OAK 36" S 16 W 25 L.
- HICKORY 7" N42 E 5 L.
- 1974 L.C.R.C., L.2, P.235, MARTIN
- 1976 L.C.R.C., L.2, P.359, MACDONALD
- 1974 SURVEY, L.1579, P. 2151, GOSS, FOUND MON. BOX

APPROVED BY PEER GROUP
 P.A. 345 OF 1990
 SAGINAW COUNTY
B-8-97 [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" REROD IN MONUMENT BOX. LOCATION VERIFIED FROM WITNESSES (L.C.R.C., L.2, P.235; L.C.R.C., L.2, P.359 AND SURVEY, L. P. 2151). MONUMENT ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 5/8" REROD IN MONUMENT BOX (LID WAS RUSTED ON). REPLACED WITH 5/8" x 18" LONG REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN NEW MONUMENT BOX.

N 60°E 43.18' SET NAIL AND TAG IN NW FACE P.P.
 N 70°E 21.45' SET CAPPED 3/8" REROD
 S 45°E 39.26' SET CAPPED 3/8" REROD
 S 45°W 42.33' SET NAIL AND TAG IN NW FACE P.P.
 S 60°W 41.45' CENTERLINE PIPELINE MARKER
 N 50°W 56.87' SET NAIL AND TAG IN NW FACE 24" MAPLE



Signed by Michael J. MacDonald

Date 9/25/97

Surveyor License No. 22438
 REMONUMENTATION

MAR 18 1998

SECTION