

SURVEY & REMONUMENTATION

MAR 18 1998

RECORDED/FILED

SAGINAW COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1997 SEP 26 P 3:30

MILDRED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

For corners in

Saginaw
(County)

Located In: BUENA VISTA

Corner Code #

LIBER 2027 PAGE 472

- 1. Public Land Survey T 13N R 5E M-11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Liber 7 Page 163
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Michael J. MacDonald, in a field survey on SEPTEMBER 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11 SET POST, J. WAMPLER D.S., 1821 ASPEN 16", N 1° E, 17.79 L.

1968 EDMANDS ENGINEERING, CONSUMERS POWER RIGHT OF WAY SURVEY, SET 3/8" REROD 1976 SURVEY, L.781, P. 544, MCGINNIS, FND 3/8" REROD 1980 SURVEY, L.1585, P. 544, MACDONALD 3/8" REROD

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY
9-18-97 *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 RESET CORNER USING WITNESSES FROM L.1585, P. 544. CORNER USED IN L.1585, P. 544 WAS RESET USING INFORMATION FROM 1968 EDMANDS ENGINEERING CONSUMERS POWER RIGHT OF WAY SURVEY. LOCATION WAS ACCEPTED AS THE BEST EVIDENCE OF THE ORIGINAL POSITION OF THE CORNER. ALSO FOUND IN THE AREA WAS A 3/8" REROD 106.46' EAST OF THE RESET M-11. THIS CORNER WAS USED IN A BAY CO. SURVEY L.1135, P. 271 AND BAY CO. SURVEY, L.1135, P. 285. ANOTHER 3/8" REROD WAS FOUND SOUTH 142', THE ONLY RECORDED INFORMATION FOR THIS POINT IS THAT IT IS A WITNESS FOR THE RESET M-11 ABOVE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 SET 5/8" x 18" LONG REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN FARM FIELD 20" BELOW THE
EAST 106.46' FOUND 3/8" REROD IN JONES ROAD
S 35° E 189.00' WEST FACE WEST SIGN LEG
S 55° E 173.75' SET NAIL AND TAG IN NORTH FACE U.P.
SOUTH 142.00' TO FOUND 3/8" REROD IN CENTERLINE KRABBE ROAD AND JONES ROAD SOUTH
S 20° W 133.51' TOP CENTERLINE PIPELINE MARKER



Signed by Michael J. MacDonald

Date 9/25/97

Surveyor's Michigan License No. 22438