

SURVEY & REMONUMENTATION

RECORDED/FILED

MAR 18 1998

SAGINAW COUNTY REMONUMENTATION

1997 SEP 26 P 3: 30

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

For corners in

Saginaw Located In: BUENA VISTA Corner Code #
(County)

LIBER 2027 PAGE 473

- 1. Public Land Survey T13N R5E M-12
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

Liber 7 Page 164

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael J. MacDonald, in a field survey on SEPTEMBER 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12 SET POST, J. WAMPLER D.S., 1821
NO TREES

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY
8-28-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 FOUND 3/4" PIPE, 5" BELOW GRAVEL SURFACE. NO OTHER MONUMENTS FOUND IN THE AREA. DISTANCE FROM SPICER NOTES (NO DATE) FITS DISTANCE FROM M13 AND DISTANCE FROM M12 TO FOUND 3/8" REROD IN CENTERLINE OF JONES ROAD AND KRABBE ROAD. MONUMENT ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M012 FOUND 3/4" PIPE 5" BELOW GRAVEL SURFACE. REPLACED MONUMENT WITH 5/8" x 18" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP 4" BELOW GRAVEL.

N 30° E 66.45' SET NAIL AND TAG IN SE FACE 36" POPLAR
N 55° E 38.50' SOUTH FACE SIGN POST
N 60° W 11.85' SOUTH FACE SOUTH SIGN LEG
N 75° W 44.97' EAST FACE PIPELINE MARKER
S 70° W 46.51' EAST FACE PIPELINE MARKER



Signed by Michael J. MacDonald Date 9/25/97

Surveyor's Michigan License No. 22438