

**SURVEY & REMONUMENTATION**

APR 14 1998

REMONUMENTATION SECTION

LIBER 2 PAGE 168

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 DEC -2 AM 9:10

LIBER NO. 2 PAGE NO. 168  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in SPEAKER TOWNSHIP

<u>Sanilac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9</u> N R <u>14</u> E	<u>C - 5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A Milletics, in a field survey on June 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C - 5	
GLO Notes	
Set Post Corner	No Old Survey Liber
Birch 20 N07 1/2° E 21	No Act 74
Sugar 18 S11W 25	Act 132 Liber 3 Page 190
	State Highway Right of Way Book
	shows monu Box in place

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C - 5  
Found Monu Box in Place with iron

REMONUMENTATION

JAN 08 1998

COMMISSION

APPROVED PEER BOARD MEETING  
NOV. 26, 1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C - 5  
NE Cor Section 18 T9N-R14E Speaker Twp.  
Monu Box in place with bolt spike iron  
S45°W 98.72 feet to a nail in a Large Power Pole  
North 6.00 feet to the centerline of pavement  
S45°E 110.0 feet to a nail in a Large Power Pole  
S30°E 39.19 feet to the west leg of a stop sign  
S20°W 91.73 feet to a road sign  
N45°E 85.65 feet to a nail in a cut off Tele Pole  
South 2632.58 feet to the E 1/4 Corner Section 18

Signed by John A Milletics  
Surveyor's Michigan License No. 25859

Date Nov 12, 1997

