

SURVEY & REMONUMENTATION

APR 14 1998

REMONUMENTATION

LIBER 2 PAGE 169

RECEIVED FOR RECORD

97 DEC -2 AM 9:10

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 169
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in SPEAKER TOWNSHIP

<u>Sanilac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T9N R14E	C - 8
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A Milletics, in a field survey on June 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C - 8
GLO Notes
Set 1/4 Section Post
Hickory 13 N43°W 7½
Elm 30 N82°E 21½

Old Survey Liber March 1890 survey
by Galbraith
Survey Act 132 Liber 4 Page 539

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C - 8
Found 5/8" Iron Bar 6" Deep in Blacktop surface

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C - 8
E 1/4 Corner Section 19 T9N-R14E Speaker Twp.
Monu Box with iron and cap
N60°E 49.71 feet to a Project Marker
N60°E 86.08 feet to a nail in a Power Pole
West 59.34 feet to a nail in a Tele Pole
S45°W 37.75 feet to the East leg of a Road Sign
N80°W 51.26 feet to a nail in a 10" Ash
North 2630.22 feet to the NE Corner Section 19

Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date Nov 12, 1997

SURVEY & REMONUMENTATION

JAN 08 1998

COMMISSION

APPROVED PEER BOARD MEETING
NOV. 26, 1997 91

