

SURVEY & REMONUMENTATION AND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

NOV 19 1993

COMMISSION FOR CORNERS OF--

LOCATED IN--

CORNER CODE NUMBER

1. PUBLIC LAND SURVEY... T. 10 N. R. 12 E. I-1, H-1
2. PROPERTY CONTROLLING IN SECTION... T. N. S., R. E. W.
3. MISCELLANEOUS PROPERTY IN SECTION... T. N. S., R. E. W.
4. LOT NO. ... RECORDED PLAT
5. PRIVATE CLAIMS

RECEIVED FOR RECORD 93 NOV -4 AM 11:58 LIBER NO. 1 PAGE NO. 386 ESTHER LEE REGISTER OF DEEDS SANILAC CO. MICHIGAN REGISTER OF DEEDS STAMP AND FILING NUMBER

I, John A. Milletics, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 5, 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law.

A. Description of original monument and accessories and/or subsequent restoration:

- I - 1 Found R/R spike in place as recorded in Liber 3 Page 485 of the Sanilac County Records.
H - 1 Found hex bolt in blacktop varied by survey dated 7-27-88

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I - 1 NE Cor Section 3 T10N-R12E Found Monu. Box
H - 1 N 1/4 Cor Section 3 T10N-R12E Found Hex Bolt

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I - 1 NE Cor Section 3 T10N-R12E Monu Box Set S45°W 58.10' to a nail in a Power Pole S45°E 43.90' to a nail in a Power Pole N70°E 49.90' to a nail in a 30" Elm
H - 1 N 1/4 Cor Section 3 T10N-R12E Monu Box Set South 56.95' to a nail in a 18" Maple S45°E 47.15' to the West end of a 12" Driveway Culvert.
Distance between I - 1, H - 1 measures 2595.56 feet

SIGNED BY [Signature] DATE Nov 1, 1993 SURVEYOR'S MICHIGAN REGISTRATION NO. 25859

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY [Signature] CHIEF OF SURVEY PARTY DATE APPROVED AND SIGNED BY [Signature] MICHIGAN REGISTERED LAND SURVEYOR DATE

SURVEYOR'S MICHIGAN REGISTRATION NO.

