

NOV 19 1993 LAND CORNER RECORDATION CERTIFICATE

COMMISSION FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. 10 N. R. 12 E.	10 N. R. 12 E.	K - 1, J - 1
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. S., R. _____ E. W.	N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.	N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

RECEIVED FOR RECORD
 93 NOV -6 AM 11:55
 LIBER NO. 1 PAGE NO. 383
 ESTHER LEE
 REGISTER OF DEEDS
 SANILAC CO., MICHIGAN
 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, John A Milletics, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 5, 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

K - 1 Found R/R spike in place in Blacktop as recorded in Liber 3 on Page 118 of the Sanilac County Records.

J - 1 Set corner at a equal distance between Corner K - 1 and I - 1 no on site evidence of existing corner found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K - 1	J - 1
NE Cor Section 2 T10N-R12E	N 1/4 Cor Section 2 T10N-R12E
Found R/R Spike	No Corner Found

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K - 1	J - 1
NE Cor Section 2 T10N-R12E	N 1/4 Cor Section 2 T10N-R12E
Monu Box Set	Monu Box Set
S45°W 42.25' to a Nail in a Tele Pole	S10°E 31.45' to a Buried Cable Sign
N10°W 60.40' to a Nail in a Power Pole	Set 1/2" iron 33.00 feet to North
N45°E 42.25' to the West leg of a Arrow Sign	
Distance between K - 1, J - 1 measures 2616.14 feet	

SIGNED BY John A Milletics DATE Nov. 1, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 25859

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

