

RECEIVED FOR RECORD

94 DEC 16 AM 9:41

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 17  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

REMONUMENTATION  
SURVEY &  
REMONUMENTATION  
APR 10 1995  
COMMISSION

For corners in  
Sanilac  
(County)

Located In: Corner Code #

1. Public Land Survey	T	10	N	R	13	E	A - 6
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A Milletics, in a field survey on Aug 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A - 6 GLO Notes  
Set 1/2 Mile Post W Oak 11 N70E 367, no other

Act 74 Forms Liber 1, Page 161

Act 132 Forme Liber 4 Page 204. Liber 2 Page 515, Liber 2 Page 514

Road Comm NONE  
Drain Comm NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 6  
E 1/4 Cor Section 18 T10N-R13E  
Found Wooden Post

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 6  
E 1/4 Cor Section 18 T10N-R13E  
Found Wooden Post - Set 1/2" Iron with Cap 25859  
S20°E 14.00 to a nail SE side of 8" Ash  
N50°E 43.80 to a nail S side of a 10" Ash  
N45°E 50.40 to a nail s side of a 10" ASG  
North 1.30 to a nail in a Fence Post

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Approved Peer Board Meeting  
Dec. 16, 1994 gm

Signed by John A Milletics

Date Dec 5, 1994

Surveyor's Michigan License No. 25859

