

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 16 AM 9:41

For corners in

Sanilac

(County)

Located In:

Corner Code #

- 1. Public Land Survey T10N R13E A - 11
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

LIBER NO. 2 PAGE NO. 22
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on Aug 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A - 11 GLO Notes
Set Post Hemlock 8 S 6 W .24, Beech 9 N 75 W 3.5
Act 74 Form NONE
Act 132 Form Liber 4 Page 806,
Road Comm NONE
Drain Comm NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 11
NW Cor Section 31 T10N-R13E
Found 1/2" Iron Bar Brass Cap #23510 in Monu Box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 11
NW Cor Section 31 T10N-R13E
Found 1/2" iron in Monu Box
S40°E 71.15' to a nail in a Power Pole
S40°E 41.40' to a 2" Pipe Road Sign
S40°W 62.70' to the face of a GTE Box
S30°W 51.50' to the face of a GTE Box

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Approved Peer Board Meeting
Dec. 16, 1994 gn

Signed by

John A Milletics

Date

Dec 5, 1994

Surveyor's Michigan License No.

25859

