

REMONUMENTATION SURVEY & REMONUMENTATION

RECEIVED FOR RECORD

94 DEC 16 AM 9:41

LAND CORNER RECORDATION CERTIFICATE

For corners in Sanilac (County)

APR 10 1995 COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 23  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Corner Code #	Recorded In:
A - 12	T 10N R 13E
	T R
	T R
	T R
	T R
	S T R
	S T R
	S T R
	S T R

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John A Milletics, in a field survey on Sept 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
A - 12 GLO Notes  
Set Post Ash 7 S 2 W .25, Beech 11 N 71 W .24

Act 74 Forms NONE  
Act 132 Forms NONE  
Road Comm. NONE  
Drain Comm. NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
A - 12  
W 1/4 Cor Section 31 T10N-R13E  
Found 1/2" iron with Brass Cap #23510 M-12 Lapeer Co.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
A - 12  
W 1/4 Cor Section 31 T10N-R13E  
Found 1/2" Iron with Brass Cap #23510  
N85°W 18.35 Notch W. End CMP  
N80°E 22.20 Notch E. End CMP  
East 54.20' nail in S. Face Power Pole

Approved Peer Board Meeting  
Dec. 16, 1994 *gm*

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by John A Milletics Date Dec. 5, 1994  
Surveyor's Michigan License No. 25859

