

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

95 JUL 10 AM 9:26

LIBER NO. 2 PAGE NO. 50
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

Remonumentation

For corners in

Sanilac

(County)

Located In:

Corner Code #

1. Public Land Survey	T10N	R 13E	B-5	C-5
	T	R		
	T	R		
	T	R		
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A Milletics, in a field survey on April 10, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-5 GLO Notes

Set Post Hemlock 9 N30E 14, Hemloch 24 S14W 29

Act 74 Form Liber 1 Page 159, Act 132 Form Liber 2 Page 515 Liber 3 Page 18

C-5 GLO Notes

Set Post Elm 22 N58°E 20, Birch 20 S59W 31

Act 74 Form Liber 1 Page 155, Act 132 Form Liber 4 Page 204, Unrecorded survey of Section 18 done for Detroit Edison.

Approved Peer Group Meeting May 25, 1995

JM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5

S 1/4 Cor Section 7 T10N-R13E
Found 5/8" Iron bar as recorded


C-5

SE Cor Section 7 T10N-R12E
Found 3/8" iron bar in pavement

SURVEY & REMONUMENTATION

JUL 31 1995

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5

S 1/4 Cor Section 7 T10N-R13E
5/8" iron bar in centerline of gravel road bed
East 94.2 to a nail in a 6" Elm
N80W 29.00 to a nail in a wooden Post
West 33.00 to a 1/2" iron bar

C-5

SE Cor Section 7 T10N-R13E
Monu Box
N45°E 53.2 to a nail in a Fence Post
S45°E 58.6 to a nail in a Fence Post
West 19.2 to the south leg of a Road Sign
S70°E 66.4 to a Road Sign

Signed by John A Milletics

Date May 21, 1995

Surveyor's Michigan License No. 25859