

RECEIVED FOR RECORD

94 DEC 16 AM 9:40

LIBER NO. 2 PAGE NO. 2  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

REMONUMENTATION  
SURVEY &  
REMONUMENTATION  
APR 10 1995  
COMMISSION

For corners in  
Sanilac  
(County)

Located In:

Corner Code --#

- 1. Public Land Survey T 10 N R 13 E C - 13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A Milletics, in a field survey on Sept 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C - 13 GLO Notes  
Set Post Ash 12 N 9½, Ash 20 N63E 15

Act 74 Form Liber 1 Page 149  
Act 132 Form Liber 3 Page 631, Liber 4 Page 387  
Road Comm None  
Drain Comm None


Approved Peer Board Meeting  
Dec. 16, 1994 jm

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C - 13  
SE Cor Section 31 T10N-R13E  
Found 1/2" iron bar  
N50°W 71.18 to a nail in a Riser Pole  
N45°E 60.48 to a nail in a POWER POLE  
N80°E 27.30 to the end of a 6' CMP  
West 16.30 to the centerline of Blacktop  
S45°W 84.35 to a nail in a Tele Pole

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C - 13  
SE Cor Section 31 T10N-R13E  
Found 1/2" Iron bar  
N50°W 71.18 to a nail in a Riser Pole  
N45°E 60.48 to a nail in a Power Pole  
N80°E 27.30 to the end of a 6' CMP  
West 16.30 to the centerline of Blacktop  
S45°W 84.35 to a nail in a Tele Pole



Signed by John A Milletics

Date Dec 5, 1994

Surveyor's Michigan License No. 25859