

Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

95 JUL 10 AM 9:26

LIBER NO. 2 PAGE NO. 51
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|---------------------------|-----------------------|
| 1. Public Land Survey | T <u>10N</u> R <u>13E</u> | <u>D-5</u> <u>E-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A Milletics in a field survey on April 10, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5 GLO Notes

Set Post at 39.79½ Hemloch 18 S53°E 26, Hemloch 9 N20°W 18
Act 74 Form Liber 1 Page 159, Act 132 Form None, Old Survey Liber None

E-5 GLO Notes

Set Post Beech 12 S18W 18, Beech 8 N40E 47. Act 74 Form Liber 1 Page 143
Act 132 Form None, Old Survey liber Page 44 April 1903

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5

S 1/4 Cor Section 8 T10N-R13E
Found 1/2" iron bar in road centerline

E-5

SE Cor Section 8 T10N-R13E
Found 1/2" iron bar in road centerline

SURVEY &
REMONUMENTATION

JUL 31 1995

COMMISSION

Approved Peer Group
Meeting May 25, 1995



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5

S 1/4 Cor Section 8 T10N-R13E
1/2" iron bar
South 23.2 to a nail box
S60°E 53.5 to a nail in a 18" Catalpa
N80°E 176.4 to a nail in a Ult Pole
N10°E 37.2 to a nail in a Fence Post

E-5

SE Cor Section 8 T10N-R13E
1/2" iron bar
N45°W 36.6 to a nail in a 18" Catalpa
S60°W 49.6 to a nail in a Fence Post
S40°W 49.1 to a nail in a Fence Post
S45°E 41.6 to a nail in a Fence Post

Signed by John A. Milletics

Date May 21, 1995

Surveyor's Michigan License No. 25859