

RECEIVED FOR RECORD

94 DEC 16 AM 9:40

LIBER NO. 2 PAGE NO. 3
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REMONUMENTATION
SURVEY &
REMONUMENTATION
APR 10 1995
COMMISSION

For corner in Sanilac (County) Located in: Corner Code #

- 1. Public Land Survey T 10 N R 13 E D - 13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A Milletics, in a field survey on Sept 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D - 13 GLO Notes
Set 1/2 Mile Post Hemlock 12 N 54 W 5 1/2, Hemlock 22 N 36 E 12 1/2

Act 74 Form Liber 1 Page 97
Act 132 Form Liber 3 Page 13, Liber 3 Page 546,

Approved Peer Board Meeting
Dec. 16, 1994 gm

Road Comm None
Drain Comm None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D - 13
S 1/4 Cor Section 32 T10N-R13E
Found 1/2" Iron Bar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D - 13
S 1/4 Cor Section 32 T10N-R13E
Found 1/2" Iron bar
West 26.22' to a 1/2" iron bar in road bed
S45°W 45.54 to a nail in a Power Pole
North 28.30 to a PK nail in a Wooden Fence Post
S75°W 79.70 to a nail in a 12" Ash



Signed by John A. Milletics

Date Dec 6, 1994

Surveyor's Michigan License No. 25859