

NOV 19 1993 LAND CORNER RECORDATION CERTIFICATE

COMMISSION FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>10</u> N. <u>13</u> E. <u>1</u>	<u>D - 1, E - 1</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

RECEIVED FOR RECORD

93 NOV -4 AM 11:54

LIBER NO. 1 PAGE NO. 379
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, John A Milletics, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 12, 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

D - 1 Set corner at a equal distance between C - 1 and E - 1
no on site evidence of existing corner found.

E - 1 Set corner using distances from C - 1 to G - 1 and survey dated
March 25-28, 1903 by Bert R. Walker.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

D - 1
N 1/4 Cor Section 5 T10N-R13E
No Corner Found

E - 1
NE Cor Section 5 T10N-R13E
No Corner Found

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D - 1
N 1/4 Cor Section 5 T10N-R13E
Monu Box Set
South 43.80' to a nail in a 30" Spruce
N45°E 63.65' to a nail in a Power Pole
N45°W 63.25' to a nail in a Power Pole

E - 1
NE Cor Section 5 T10N-R13E
Monu Box Set
East 4.33' to the SW Cor Section 32 T11N-R13E
N10°E 65.63' to a nail in a Power Pole
N10°W 65.50' to a nail in a Power Pole
S45°E 29.90' to the SW Cor of a Headwall

SIGNED BY John A Milletics DATE Nov 4, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 25859

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

