

RECEIVED FOR RECORD

94 DEC 16 AM 9:40

REMONUMENTATION SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners

Sanilac (County)

Located In:

Corner Code #

LIBER NO. 2 PAGE NO. 4 ESTHER LEE REGISTER OF DEEDS SANILAC CO., MICHIGAN

- 1. Public Land Survey T 10N R 13 E E - 13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is present in row 12, column C.

I, John A Milletics, in a field survey on April 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: E - 13 GLO Notes. Set Post Ash 12 N 25 W 36, Elm 16 N 61 E

Approved Peer Board Meeting Dec. 16, 1994 gm

Act 74 Forms Liber 1 Page 97, Liber 1 Page 270
Act 132 Forms Liber 1 Page 283, Liber 1 Page 88
Liber 3 Page 14 Liber 3 Page 514
Road Comm NONE
Drain Comm None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: E - 13 SW Cor Section 33 T10N-R13E Found 5/8" Iron Bar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: E - 13 SW Cor Section 33 T10N-R13E Found 5/8" Iron Bar West 16.50 to a 1/2" Iron bar(NW Cor Section 4) N45°E 56.3 to a nail se Side of a Fence Post S45°E 48.35 to a nail NE Side of a Tele Pole N45°W 81.80 to a nail SW Side of a Power Pole



Signed by John A. Milletics

Date Dec 6, 1994

Surveyor's Michigan License No. 25859