

SURVEY &
 REMONUMENTATION
 APR 10 1995
 COMMISSION

RECEIVED FOR RECORD

94 DEC 16 AM 9:40

REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 5
 ESTHER LEE
 REGISTER OF DEEDS
 SANILAC CO., MICHIGAN

For corners of _____ Located In: _____ Corner Code # _____
 Sanilac (County)

- 1. Public Land Survey T 10 N R 13^E F - 13
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A. Milletics in a field survey on April 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 F - 13 GLO Notes
 Set 1/2 Mile Post Birch 9 N 47 1/2 W 35, Maple 15 N 7 E 10
- Act 74 Forms None
 Act 132 Forms Liber 1, Page 283, Liber 1 Page 88
- Road Comm None
 Drain Comm None

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Approved Peer Board Meeting
 Dec. 16, 1994 *JM*

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 F - 13
 S 1/4 Cor Section 33 T10N-R13E
 Found no evidence on corner in road bed
 Set 1/2" Iron Bar on line at equal distances 2629.54'

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 F - 13
 S 1/4 Cor Section T10N-R13E
 Set 1/2" Iron bar with cap 25859
 East 2629.54' to the SE Cor Section 33
 West 2629.54' to the SW Cor Section 33
 East 5.37' to a 1/2" Iron Bar (the N 1/4 Cor Section 4)
 S10°E 84.50' to a nail north side of a 8" Ash
 N45°W 123.88' to a nail East side of a Power Pole
 S50°W 64.35' to a nail North side of a 6" Ash



Signed by John A. Milletics Date Dec 5, 1994
 Surveyor's Michigan License No. 25859