

1993

LIBER 1 PAGE 424

REMONUMENTATION COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Sanilac

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 10N R 13E
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

J - 1, I - 1

leg 1

RECEIVED FOR RECORD

93 DEC 29 AM 10:54

LIBER NO. 1 PAGE NO. 424
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A Milletics in a field survey on Dec 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J - 1

Found P.K. nail in the centerline of paved surface, per survey dated 2-5-90

I - 1

Found P.K. nail in the centerline of paved surface, per survey recorded in Liber 4 on Page 303 of the Sanilac County Records

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J - 1

N 1/4 Cor Section 2 T10N-R13E
Found P.K. nail

I - 1

NW Corner Section 2 T10N-R13E
Found P.K. nail

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J - 1

N 1/4 Cor Section 2 T10N-R13E
Set Monu Box
East 62.00' to the S 1/4 Cor Section 34
N50°E 70.25' to a nail in a Fence Post
South 33.10' to a nail in a Fence Post
N30°E 39.45' to the West end of a 12" CMP

I - 1

NW Cor Section 2 T10N-R13E
Set Monu Box
North 20.55' to the West leg of a Road Sign
S40°E 90.55' to a Michigan Bell Box
East 48.92' to the SE Cor Section 33
S45°W 77.55' to a 4" Riser Pipe

Signed by John A Milletics

Date Dec. 24, 1993

Surveyor's Michigan License No. 25859