

NOV 21 1997

LIBER

2 PAGE 146

RECEIVED FOR RECORD

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

97 SEP -9 AM 8:58

LIBER NO. 2 PAGE NO. 146

ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac

(County)

Located In:

Corner Code #

1. Public Land Survey

T10N R13E

I - 1

T R

T R

T R

T R

Sec. 2

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John A Milletics, in a field survey on June 21, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I - 1

GLO Notes

Black Ash 10 , S39W 21

Tamarack 7 , S38E 7

APPROVED PEER BOARD MEETING

Aug 18, 1997 gm

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I - 1

Found Monu Box - removed by Sanilac Co. Road Comm. during reconstruction of road, REPLACED using Act 74 recording Liber 1 Page 424

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I - 1

NW Corner Section 2 T10N-R13E

Monu Box with iron and cap

East 48.92 feet to the SE Cor Section 33 (MONU Box)

S40W 73.00 to a Riser Box

S45E 46.76 to a stop sign

S40E 90.55 to a Michigan Bell Box

East 2632.90 to the N 1/4 Corner Section 2

Signed by

John A Milletics

Date Aug 11, 1997

Surveyor's Michigan License No. 25859

| | | | | | | | | | | | | | | |
|----|----|---|---|----|---|---|----|---|----|---|---|----|---|----|
| | A | B | C | D | E | F | G | H | I | J | K | L | M | |
| 1 | | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | | 4 | | 3 | | | 2 | | 1 |
| 3 | | | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | | 9 | | 10 | | | 11 | | 12 |
| 5 | | | | | | | | | | | | | | |
| 6 | 10 | | | 17 | | | 16 | | 15 | | | 14 | | 13 |
| 7 | | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | | 21 | | 22 | | | 23 | | 24 |
| 9 | | | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | | 28 | | 27 | | | 26 | | 25 |
| 11 | | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | | 33 | | 34 | | | 35 | | 36 |
| 13 | | | | | | | | | | | | | | |

