

1993

REMONUMENTATION COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac (County) Located In: Corner Code #

1. Public Land Survey	T <u>10N</u> R <u>13E</u>	L - 1, <u>K - 1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>Seg 1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD

93 DEC 29 AM 10:54

LIBER NO. 1 PAGE NO. 425
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on Dec 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L - 1

Found Railroad spike in centerline of pavement, per survey dated 1-26-84 Kay Eng.

K - 1

Found Railroad spike in centerline of pavement, per survey dated 2-5-1990

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L - 1

N 1/4 Cor Section 1 T10N-R13E
Found Railroad spike

K - 1

NW Cor Section 1 T10N-R13E
Found Railroad spike

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L - 1

N 1/4 Cor Section 1 T10N-R13E
Set Monu Box
North 19.45' to the East leg of a Road Sign
N45°E 58.55' to a nail in a Power Pole
S40°E 40.40' to a Stop Sign
East 82.55' to the S 1/4 Cor Section 35

K - 1

NW Cor Section 1 T10N-R13E
Set Monu Box
North 19.70' to the East leg of a Road Sign
S30°E 38.20' to a Stop Sign
N60°E 135.3' to a nail in a Tele Pole
East 75.15' to the SE Cor Section 34

Signed by John A Milletics Date Dec. 24, 1993

Surveyor's Michigan License No. 25859