

NOV 21 1997

COMMISSION

LIBER 2 PAGE 149

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
97 SEP -9 AM 8:58  
LIBER NO. 2 PAGE NO. 149  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

Sanilac  
(County)

Located In:

Corner Code #

1. Public Land Survey

T10NR13E L-1

2. Property Controlling in Section

S T R leg-2

3. Miscellaneous Property in Sec.

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

John A Millettics, in a field survey on June 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L - 1  
NO GLO Notes Available

APPROVED PEER BOARD MEETING  
Aug 18, 1997 *JM*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L - 1  
Found Monu Box - removed by Sanilac County Road Comm. during reconstruction of Road, REPLACED using Act 74 recorded Liber 1 Page 425

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

L - 1  
N 1/4 Cor Section 1 T10N-R13E  
Moun Box with iron & cap  
East 82.55 to the S 1/4 Corner Section 35 (MONU BOX)  
N05°E 19.35 to the East Leg of a Road Sign  
N05°W 19.55 to the West Leg of a Road Sign  
N45°E 58.55 to a nail in a Power Pole  
S40°E 40.40 to a stop sign  
East 2636.00 to the NE Cor Section 1  
West 2652.48 to the NW Cor Section 1

Signed by *JAM*  
Surveyor's Michigan License No. 25859

Date Aug 11, 1997

