

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 AUG 12 PM 2:38

LIBER NO. 1 PAGE NO. 474
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 10N R 13E M - 6, M - 7
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A Milletics, in a field survey on July 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M - 6 Found 5/8" iron bar in gravel road bed, raised with 1/2" iron bar

M - 7 Found 1/2" iron bar in gravel road bed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 6
E 1/4 Corner Section 13 T10N-R13E
Found 5/8" iron bar

M - 7
SE Corner Section 13 T10N-R13E
Found 1/2" iron bar

SURVEY &
REMONUMENTATION

SEP 07 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 6
E 1/4 Corner Section 13 T10N-R13E
1/2" Iron Bar
West 18.30 to a nail S side of a Fence Post
East 7.0 to the centerline of the gravel road
North 2632.60' to the NE Cor Section 13
South 2637.06' to the SE Cor Section 13

M - 7
SE Corner Section 13 T10N-R13E
1/2" iron bar
East 31.15' to a nail N side of a Fence Post
S70°E 18.75 to the S. Leg of a Road Sign
S45°W 85.00 to a nail SE Side of a Power Pole
S70°W 42.30 to a stop sign

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Approved Peer Board Meeting
Aug. 9, 1994 *[Signature]*

Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date July 23, 1994