

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 AUG 12 PM 2: 38

LIBER NO. 1 PAGE NO. 475
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 10 N 13 E M - 8, M - 9
T R
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

John A Milletics, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M - 8 Found 5/8" Iron bar, raised with 1/2" iron, in gravel road bed

M - 9 Found 1/2" Iron bar in gravel road bed

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Approved Peer Board Meeting
Aug. 9, 1994

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M - 8 M - 9
- E 1/4 Cor Section 24 T10N- R13E SE Cor Section 24 T10N-R13E
- Found 5/8" iron bar Found 5/8" iron bar

SURVEY &
REMONUMENTATION

SEP 07 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M - 8 M - 9
- E 1/4 Cor Section 24 T10N-R13E SE Cor Section 24 T10N-R13E
- 1/2" iron bar 1/2" Iron Bar
- East 25.30 to a nail S side of a Fence Post N40°E 75.20 to a nail SW side of a Power Pole
- West 66.00 to a nail S side of a Power Pole N45°W 101.0 to a nail SW side of a Power Pole
- N45°W 53.4 to a nail NW side of a 6" Pine S50°W 34.40 to a stop sign
- South 2640.76' to the SE of 24 N50°W 34.70 to a stop sign
- North 2640.76' to the E 1/4 Cor Sec 24

Signed by John A Milletics Date July 23, 1994
Surveyor's Michigan License No. 25859