

94 AUG 12 PM 2:39

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 1 PAGE NO. 477
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 10N R 13E M - 12, M - 13
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

John A Milletics July 8 94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M - 12 Found 1/2" Iron in gravel road bed as recorded in Liber 3 on Page 610 of the Sanilac County Records.

M - 13 Found 1" Iron Bar in gravel road bed.

Approved Peer Board Meeting
Aug. 9, 1994

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 12
E 1/4 Cor Section 36 T10N-R13E
Found 1/2" Iron Bar

M - 13
SE Cor Section 36 T10N-R13E
Found 1" Bar in gravel road bed.

SURVEY &
REMONUMENTATION

SEP 07 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 12
E 1/4 Cor Section 36 T10N-R13E
1/2" Iron Bar
S50°E 36.40 to a nail SW side of a 18" Ash
East 70.40 to a nail S side of a Power Pole
West 29.80 to a nail S side of a Fence Post
N30°E 43.00 to the N End of a 12" CMP

M - 13
SE Cor Section 36 T10N-R13E
1" Iron Bar
N35°E 68.00 to a nail NW side of a 24" Ash
S50°W 83.00 to the NE Cor of a House
S40°E 104.4 to the NW Cor of a Shed
S45°W 37.50 to a stop sign

Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date July 23, 1994