

NOV 21 1997

LIBER

PAGE 147

RECEIVED FOR RECORD

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

97 SEP -9 AM 8:58

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 147

For corners in

Sanilac

(County)

Located in:

Corner Code #

1. Public Land Survey

T 10N R 13E

J - 1

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on June 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J - 1  
NO GLO NOTES Availible

APPROVED PEER BOARD MEETING

Aug 18, 1997 JM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J - 1  
Found Monu Box - removed by Sanilac Co. Road Comm. during reconstruction of road, REPLACED using Act 74 recording Liber 1, Page 424

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J - 1  
N 1/4 Corner Section 2 T10N-R13E  
Monu Box with iron and cap  
East 62.00 to the S 1/4 Corner Section 34 (MONU BOX)  
N50°E 70.65 to a nail in a Fence Post  
South 33.10 to a nail in a Fence Post  
N40°E 39.45 to top West end of a 12" CMP.  
East 2632.90 to the NE Cor Section 2  
West 2632.90 to the NW Cor Section 2

Signed by [Signature]  
Surveyor's Michigan License No. 25859

Date Aug 11, 1997

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

