

NOV 21 1997

LIBER

2 PAGE 148

COMMISSION

REMOUNMENTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 SEP -9 AM 8:58

LIBER NO. 2 PAGE NO. 148

ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac

(County)

Located In:

Corner Code #

1. Public Land Survey

T10N R13E

K - 1

T R

T R

T R

T R

2. Property Controlling
in Section

S

T R

deq 2

3. Miscellaneous
Property in Sec.

S

T R

S

T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, John A Millettics, in a field survey on June 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

K - 1

GLO Notes

Birch 12, S79E 45 1/2

Birch 10 S09W 6

APPROVED PEER BOARD MEETING

Aug 18, 1997 Jm

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K - 1

Found Monu Box - removed by Sanilac County Road Comm. during reconstruction of road, REPLACED using Act 74 recording Liber 1 Page 425

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K - 1

NW Corner Section 1 T10N-R13E

Moun Box with iron & cap

East 75.15 to the SE Corner Section 34 (MONU BOX)

N60°E 135.30 to a nail in a Tele Pole

S30°E 38.20 to a Stop Sign

N45°E 68.42 to a Stop Sign

N05°W 19.56 to West leg of a Road Sign

N05°E 19.59 to East leg of a Road Sign

East 2652.48 to the N 1/4 Corner Section 1

Signed by *J.A. Millettics*

Surveyor's Michigan License No. 25859

Date Aug 11, 1997

