

REMONUMENTATION

LIBER

2 PAGE 122

RECEIVED FOR RECORD

NOV 2 1 1997

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

97 SEP -9 AM 8:56

COMMISSION

LIBER NO. 2 PAGE NO. 122

ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

<u>Sanilac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T10N R14E	A - 1
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A Milletics, in a field survey on June 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

A - 1  
GLO Notes  
Hemlock 9 S22W 12  
Hemlock 9 S57E 21

APPROVED PEER BOARD MEETING  
Aug 18, 1997 JM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 1  
Found Monu Box - removed by Sanilac County Road Comm, during reconstruction of Road, REPLACED using Act 74 recorded in Liber 1 Page 426

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 1  
NW Corner Section 6 T10N-R14E  
Monu Box with iron and cap  
East 106.68 to the SE Corner Section 35 (MONU BOX)  
S45°E 100.50 to a nail in a Power Pole  
N40°E 78.93 to a riser box  
N60°E 99.06 to a stop sign  
N45°E 80.00 to a nail in a Power Pole  
East 972.06 to the N 1/4 Cor Section 6



Signed by [Signature]  
Surveyor's Michigan License No. 25859

Date Aug 11, 1997