

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 AUG 12 PM 2:38

LIBER NO. 1 PAGE NO. 473
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac

(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 10N R 14E A - 4, A - 5
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

John A Milletics, in a field survey on July 6, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A - 4 Found no corner in gravel road bed

A - 5 Found 1" bar as recorded in Liber 3 on Page 418 of the Sanilac County Records.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Approved Peer Board Meeting
Aug. 9, 1994

[Signature]
gm

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 4
W 1/4 Cor Section 7 T10N-R14E
Set 1/2" Iron Bar

A - 5
SW Cor Section 7 T10N-R14E
Found 1" Iron Bar

SURVEY &
REMONUMENTATION

SEP 07 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 4
W 1/4 Cor Section 7 T10N-R14E
1/2" Iron Bar
North 19.11' to a 1" iron bar being the E 1/4
Cor Section 12 T10N-R13E
S75°W 27.72 to a nail on the NW side of a 24" Ash
N60°W 84.40 to a nail on the SW side of a Power Pole
N80°W 30.95 to a stop sign
South 2660.39 to the SW cor Sec 7

A - 5
SW Cor Section 7 T10N-R14E
1" Iron Bar
North 38.22 to a 1/2" iron bar being the
SE Cor Section 12 T10N-R13E
N30°W 79.10 to a nail NE side of a 18"
Catalpa
N50°W 87.30 to a nail NE side of a Power
Pole
N45°E 47.30 to a stop sign
N60°W 41.90 to a stop sign

Signed by *[Signature]*

Date July 23, 1994

Surveyor's Michigan License No. 25859