

SURVEY &  
REMONUMENTATION

1993  
REMONUMENTATION

LIBER 1 PAGE 426

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

<u>Sanilac</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T 10N R 14E	<u>B-1, A-1</u>
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	<u>leg. 1</u>
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD

93 DEC 29 AM 10:54

LIBER NO. 1 PAGE NO. 426  
EUTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on Dec 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

B - 1

Found P.K. nail in centerline of paved surface, survey dated 6-26-89

A - 1

Found P.K. nail in centerline of paved surface, per survey comp from survey dated 4-17-71 Kay Engineering

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B - 1

N 1/4 Cor Section 6 T10N-R14E  
Found P.K. nail

A - 1

NW Cor Section 6 T10N-R14E  
Found P.K. nail

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B - 1

N 1/4 Cor Section 6 T10N-R14E  
Set Monu Box  
N50°W 110.55' to a Power Pole  
South 55.95' to a 8" Maple  
S20°E 21.40' to the East end of a 12" CMP  
West 972.06' to the NW Cor Section 6

A - 1

NW Cor Section 6 T10N-R14E  
Set Monu Box  
S45°E 100.50' to a nail in a Power Pole  
S75°E 107.95' to the West Leg of a Road Sign  
N45°E 80.00' to a nail in a Power Pole  
East 106.68' to the SE Cor Sec 35

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by John A Milletics

Date Dec 24, 1993

Surveyor's Michigan License No. 25859