

Remonumentation

LIBER

2 PAGE 47

RECEIVED FOR RECORD

95 JUL 10 AM 9:25

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 47

ESTHER LEE REGISTER OF DEEDS SANILAC CO., MICHIGAN

For corners in

Sanilac (County)

Located In:

Corner Code #

- 1. Public Land Survey T 10N R 14E C-5 D-5
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

SURVEY & REMONUMENTATION

JUL 31 1995

COMMISSION

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on April 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-5 GLO Notes

Set Post Hemlock 11 S78 1/2 E 22, Hemlock S87 1/2 W 12

Act 74 Form none Act 132 Form Liber 4 Page 77, Liber 3 Page 480, Liber 4 Page 150

Old Survey Liber page 122 Aug 1885, Page 126 April 24, 1884

D-5 GLO Notes

Set Post at 39.78 Chains Hemlock 13 N9W 38, Hemlock 13 S48E 11

Act 74 Form None, Act 132 Form Liber 4 Page 150, Liber 3 Page 480

Approved Peer Group Meeting May 25, 1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5

SE Cor Section 7 T10N-R14E

Found 1/2" Iron bar in pavement

D-5

S 1/4 Cor Section 8 T10N-R14E

Found 1/2" Iron bar in gravel road bed



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5

SE Cor Section 7 T10N-R14E

Monu Box

N40°W 78.0 to a nail in a Power Pole

N40°E 73.2 to a nail in a Power Pole

S50°E 51.8 to a nail in a Power Pole

S60°W 43.0 to a stop sign

D-5

S 1/4 Cor Section 8 T10N-R14E

1/2" Iron Bar

South 27.30 to a nail in a Fence Post

South 55.80 to a nail in a Power Pole

N50°E 92.35 to a nail in a Power Pole

N30°E 65.40 to a nail in a 10" Apple

Signed by John A Milletics

Date May 23, 1995

Surveyor's Michigan License No. 25859