

RECEIVED FOR RECORD

94 DEC 16 AM 9:40

LIBER NO. 1 PAGE NO. 487  
 ESTHER LEE  
 REGISTER OF DEEDS  
 SANILAC CO., MICHIGAN

REMONUMENTATION  
 SURVEY &  
 REMONUMENTATION  
 APR 10 1995  
 COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in \_\_\_\_\_  
 Sanilac (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T 10N R 14E	C - 13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on Aug 14, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 C - 13 GLO Notes  
 Set Post Corner Birch 11 N 13 W 13, Birch 11 N54 1/2 E 16  
 Act 74 Form NONE  
 Act 132 Form Liber 3, Page 610  
 Unrecorded Survey Dated 8-2-1979  
 Road Comm NONE  
 Drain Comm NONE

Approved Peer Board Meeting  
 Dec. 16, 1994 92

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 C - 13  
 SE Cor Section 31 T10N-R14E  
 Found 1/2" Iron Bar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 C - 13  
 SE Cor Section 31 T10N-R14E  
 Found 1/2" Iron Bar  
 East 21.00' to C/L of Blacktop  
 S45°W 31.55 to a Project Marker  
 S45°W 37.62 to a nail in a Power Pole  
 S10°E 36.81 to a Road Sign  
 S40°E 70.70 to a Project Marker  
 S45°E 97.50 to a nail in a Tele Pole



Signed by John A Milletics Date Dec 7, 1994  
 Surveyor's Michigan License No. 25859